


**NOTES:**

1. EXTENSIONS ARE REQUIRED WHEN THE VALVE NUT IS MORE THAN FOUR (4) FEET BELOW FINISHED GRADE. EXTENSIONS ARE TO BE A MINIMUM OF ONE (1) FOOT LONG. **ONLY ONE EXTENSION TO BE USED PER VALVE.**
2. VALVE BOX EXTENSIONS SHALL BE 5" C.I. SOILS PIPE-TYLER TY SEAL
3. ALL EXTENSIONS ARE TO BE MADE OF STEEL, SIZED AS NOTED, AND PAINTED WITH 2 COATS OF METAL PAINT.
4. RAISE THE VALVE BOX TO FINISH GRADE AFTER ASPHALT CONCRETE WORK IS COMPLETED BUT IN NO CASE LATER THAN 48 HOURS.
5. EARS OF THE VALVE BOX TOP SECTION WILL BE INSTALLED INDICATING SANITARY SEWER MAIN DIRECTION.
6. VALVE BOX OUTSIDE PAVED AREA, A CONCRETE PAD SHALL BE INSTALLED (2' x 2' x 4")

	<p><b>City of Bremerton</b></p> <hr style="width: 50%; margin: auto;"/> <p><b>PUBLIC WORKS</b></p> <hr style="width: 50%; margin: auto;"/> <p><b>DESIGN/CONSTRUCTION STANDARDS</b></p>	<p><b>SANITARY SEWER</b></p> <p><b>CAST IRON VALVE BOX ASSEMBLY</b></p>	<p><b>6130</b></p>
	<p><small>Alteration of this drawing is prohibited. Any approval of an altered drawing is unauthorized and void.</small></p>		<p>Revision Date <b>3/03/15</b></p>